

## **PAY ITEM QUANTITY CALCULATIONS**

*INSTALLATION OF PAVEMENT MARKINGS AT VARIOUS LOCATIONS IN THE  
BUFFALO AND SYRACUSE DIVISIONS*

TAB 23-29  
D214952  
PIN B53074

## INSTALLATION OF PAVEMENT MARKINGS AT VARIOUS LOCATIONS IN THE BUFFALO AND SYRACUSE DIVISIONS

ITEM NUMBER	ITEM DESCRIPTION	UNITS	QUANTITY
619.0101	BASIC WORK ZONE TRAFFIC CONTROL (DAILY OPERATIONS)	LS	1
619.24	NIGHTTIME OPERATIONS	LS	1
635.01030625	CLEANING AND PREPARATION OF PAVEMENT SURFACES - 6" WIDTH LINES	LF	1,000
635.0203	CLEANING AND PREPARATION OF PAVEMENT SURFACES - LETTERS	EA	42
635.0303--25	CLEANING AND PREPARATION OF PAVEMENT SURFACES - SYMBOLS	EA	50
635.0402--25	MISCELLANEOUS ABRADING OF EPOXY PAVEMENT STRIPES	LF	1,000
640.25000010	BLUE REFLECTORIZED PAVEMENT MARKING PAINT FOR HANDICAPPED PARKING SPACES	LF	160
685.0106--25	WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS	LF	172,568
685.0206--25	YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS	LF	82,658
685.1306--25	WHITE EPOXY REFLECTORIZED PAVEMENT LETTERS	EA	42
685.1406--25	WHITE EPOXY REFLECTORIZED PAVEMENT SYMBOLS	EA	50
685.15----25	BLACK EPOXY PAVEMENT MARKINGS	LF	60,000
685.1707--25	WHITE HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPES - 6 IN. x 20 MILS	LF	1,041,850
685.1708--25	YELLOW HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPES - 6 IN. x 20 MILS	LF	830,500



**Thruway  
Authority**

PROJECT: Installation of Pavement Markings at Various      MADE BY: J. McCool      DATE: 09/2023  
Locations in the Buffalo and Syracuse Divisions      CHECKED BY: TJW      DATE: 11/8/2023

SUBJECT: WZTC      SHEET # 1 OF 1

---

---

**ITEM 619.0101 - BASIC WORK ZONE TRAFFIC CONTROL (DAILY OPERATIONS) (LS)**

**1 LS**



**Thruway  
Authority**

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Nighttime Operations

SHEET # 1 OF 1

---

---

**ITEM 619.24 - NIGHTTIME OPERATIONS (LS)**

**1 LS**



**Thruway  
Authority**

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Cleaning and Prep of Pavement

SHEET # 1 OF 1

---

---

**ITEM 635.01030625 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - 6" WIDTH LINES (LF)**

Item is to be used A.O.B.E.

**SAY: 1,000 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Cleaning and Prep of Pavement - Letters

SHEET # 1 OF 1

---

---

ITEM 635.0203 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - LETTERS (EA)

Interchange 45

6 " O "

6 " N "

6 " L "

5 " Y "

2 " T "

1 " A "

1 " D "

1 " E "

1 " M "

29 total letters

Interchange 46

2 " O "

2 " N "

2 " L "

1 " Y "

2 " T "

1 " A "

1 " D "

1 " E "

1 " M "

13 total letters

SAY: 42 EA



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Cleaning and Prep of Pavement - Symbols

SHEET # 1 OF 1

---

---

**ITEM 635.0303--25 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - SYMBOLS (EA)**

Interchange 45

- 2 Left Only Arrows
- 2 Right Only Arrows
- 3 Lane Reduction Arrows

Additional Striping @ Interchange 48

- 2 Left Only Arrows
- 1 Right Only Arrow
- 1 Straight Arrow

Additional Striping @ Interchange 48A

- 4 Left Only Arrows
- 2 Right Only Arrows

Mainline MP 349.6 - 378.2

- 4 Lane Reduction Arrows

Interchange 46

- 4 Straight Arrows
- 15 Yield Bar Triangles

Text Stop @ MP 353.10 EB

- 2 Handicapped Parking Symbols

Ontario Service Area

- 1 Handicapped Parking Symbol

Additional Striping @ Interchange 47

- 1 Lane Reduction Arrow

Interchange 49

- 2 Left Only Arrows
- 2 Right Only Arrow
- 2 Left/Straight Arrows

**SAY: 50 EA**



**Thruway  
Authority**

PROJECT: Installation of Pavement Markings at Various      MADE BY: J. McCool      DATE: 09/2023  
Locations in the Buffalo and Syracuse Divisions      CHECKED BY: TJW      DATE: 11/8/23

SUBJECT: Misc. Abrading of Epoxy Stripes      SHEET # 1 OF 1

---

---

**ITEM 635.0402--25 - MISCELLANEOUS ABRADING OF EPOXY PAVEMENT STRIPES (LF)**

Item is to be used A.O.B.E.

**SAY:    1,000    LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023


CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Blue Pavement Marking Paint

SHEET # 1 OF 1

ITEM 640.25000010 - BLUE REFLECTORIZED PAVEMENT MARKING PAINT FOR HANDICAPPED PARKING SPACES (LF)



4" per pass

$48" / 4" \text{ per pass} = 12 \text{ passes}$

$12 \text{ passes at } 48" = 576" / 12" = 48 \text{ ft per symbol}$

$48 \text{ ft per symbol} \times 3 \text{ symbols} = 144 \text{ ft}$

$144 \text{ ft} \times 5\% = 160 \text{ LF}$

SAY: 160 LF



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: White Epoxy Stripe

SHEET # 1 OF 1

---

---

ITEM 685.0106--25 - WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)

\*\*All measurements were  
taken using Google Earth\*\*

Location

Interchange 40	15,768	LF
Rest Area @ MP 318 WB	3,811	LF
Interchange 41	16,627	LF
Interchange 45	36,811	LF
Text Stop @ MP 353.10 EB	4,810	LF
Interchange 46	38,389	LF
Scottsville Service Area	4,034	LF
Ontario Service Area	3,502	LF
Add'l Striping @ Interchange 47	9,560	LF
Add'l Striping @ Interchange 48	2,431	LF
Add'l Striping @ Interchange 48A	3,067	LF
Interchange 49	25,540	LF
	<hr/>	
	164,350	LF

$$164,350 \quad x \quad 5\% \quad = \quad 172,568$$

SAY: 172,568 LF



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Yellow Epoxy Stripe

SHEET # 1 OF 1

---

---

ITEM 685.0206--25 - YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)

\*\*All measurements were  
taken using Google Earth\*\*

Location

Interchange 40	7,644	LF
Rest Area @ MP 318 WB	675	LF
Interchange 41	7,898	LF
Interchange 45	14,542	LF
Text Stop @ MP 353.10 EB	1,059	LF
Interchange 46	17,232	LF
Scottsville Service Area	3,106	LF
Ontario Service Area	4,547	LF
Add'l Striping @ Interchange 47	5,511	LF
Add'l Striping @ Interchange 48	1,836	LF
Add'l Striping @ Interchange 48A	3,610	LF
Interchange 49	11,062	LF
	<hr/> 78,722	LF

$$78,722 \quad x \quad 5\% \quad = \quad 82,658$$

SAY: 82,658 LF



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 40 (MP 304.19)  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

White

EB Decel  $798 + 1,323 = 2,121$

WB Decel  $921 + 2,563 = 3,484$

EB Accel  $1,542 + 1,045 = 2,587$

WB Accel  $1,674 + 2,631 = 4,305$

Gores  $94 + 249 + 280 + 223 + 188 + 413 + 164 = 1,611 \times 2 = 3,222$

Skip  $195 \times 0.25 = 49$

$2,121 + 3,484 + 2,587 + 4,305 + 3,222 + 49 = 15,768$

Yellow

EB Decel 869

WB Decel 2,946

EB Accel 1,006

WB Accel 2,823

$869 + 2,946 + 1,006 + 2,823 = 7,644$



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 41 (MP 320.41)  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

White

EB Decel  $1,048 + 1,346 = 2,394$

WB Decel  $1,114 + 2,549 = 3,663$

EB Accel  $1,485 + 1,163 = 2,648$

WB Accel  $1,665 + 2,730 = 4,395$

Gores  $315 + 216 + 275 + 351 + 219 + 348 = 1,724 \times 2 = 3,448$

Skip  $313 \times 0.25 = 79$

$2,394 + 3,663 + 2,648 + 4,395 + 3,448 + 79 = 16,627$

Yellow

EB Decel 823

WB Decel 3,014

EB Accel 1,075

WB Accel 2,986

$823 + 3,014 + 1,075 + 2,986 = 7,898$

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 45 (MP 350.99)  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White**

Tandem Lot  $440 + 1,317 + 289 = 2,046$

I-490 Ramps  $2,035 + 94 + 120 = 2,249$

I-490  $1,310 + 477 = 1,787$

Gore  $1,014 + 639 + 227 + 696 + 261 + 388 + 181 + 365 + 418 + 202 + 205 + 115 + 112 + 128 = 4,951$   
 $4,951 \times 2 = 9,902$

Skip  $767 + 1,070 + (422 \times 2) + 2,426 + 1,031 + (607 \times 2) + 1,867 + 993 + 50 = 10,262$   
 $9,780 \times 0.25 = 2,566$

Stop Bar  $46 \times 4 = 184$

Ramp Arrow  $1 \times 74 = 74$

WB Decel  $1,019 + 1,464 = 2,483$

EB Decel  $3,490$

EB Accel  $6,660$

WB Accel  $5,370$

$2,046 + 2,249 + 1,787 + 9,902 + 2,566 + 184 + 74 + 2,483 + 3,490 + 6,660 + 5,370 = 36,811$

**Yellow**

WB Decel  $498 + 283 = 781$

EB Decel  $5,240$

EB Accel  $5,560$

WB Accel  $743$

I-490 Ramps  $1,668 + 411 + 139 = 2,218$

$781 + 5,240 + 5,560 + 743 + 2,218 = 14,542$



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 46 (MP 362.44)  
White/Yellow Epoxy Stripes

SHEET # 1 OF 2

White

I-90 WB Accel	$1,151 + 1,695 = 2,846$
I-90 WB Decel	$964 + 826 + 1,034 = 2,824$
I-90 EB Decel	$2,533 + 1,120 = 3,653$
I-90 EB Accel	$1,771 + 2,062 = 3,833$
I-390 NB Off Ramp	$1,410 + 1,494 = 2,904$
I-390 NB On Ramp	$1,531 + 1,007 + 1,289 = 3,827$
I-390 SB Off Ramp	$886 + 1,085 = 1,971$
I-390 SB On Ramp	$744 + 250 = 994$
Tandem / Maintenance Lot	$666 + 741 + 569 + 185 + 184 = 2,345$
Gore	$293 + 620 + 82 + 264 + 417 + 82 + 506 + 325 + 399 + 734 + 154 + 287 + 195 + 201 + 439 + 657 + 183 + 123 + 55 + 145 = 6,161 \times 2 = 12,322$
Skip	$88 + 468 + 506 + 644 + 644 = 2,350 \times 0.25 = 588$
Ramp Arrow	$3 \times 74 = 222$
Stop Bar	$15 \times 4 = 60$
Yield Bar Triangles	15
	$2,846 + 2,824 + 3,653 + 3,833 + 2,904 + 3,827 + 1,971 + 994 + 2,345 + 12,322 + 588 + 222 + 60 = 38,389$





PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/9/2023

SUBJECT: Interchange 46 (MP 362.44)  
White/Yellow Epoxy Stripes

SHEET # 2 OF 2

Yellow

I-90 WB Accel	536
I-90 WB Decel	609
I-90 EB Decel	$2,861 + 825 = 3,686$
I-90 EB Accel	$2,711 + 823 = 3,534$
I-390 NB Off Ramp	$1,745 + 1,048 = 2,793$
I-390 NB On Ramp	$1,725 + 1,472 = 3,197$
I-390 SB Off Ramp	899
I-390 SB On Ramp	654
Tandem / Maintenance Lot	$(182 \times 2) + 107 + 236 + 313 + 60 + 181 + 63 = 1,324$
$536 + 609 + 3,686 + 3,534 + 2,793 + 3,197 + 899 + 654 + 1,324 = 17,232$	





PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 47 (MP 378.56) Additional  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White**

Maintenance Lot 1,081

I-490  $526 + 233 + 1,712 + 434 + 801 = 3,706$

Ramp 614

Gores  $55 + 63 + 116 + 114 + 74 + 112 + 198 + 360 + 318 + 224 = 1,634 \times 2 = 3,268$

Skip  $192 + 654 + 588 + 1,040 = 2,474 \times 0.25 = 619$   
 $543 \times 0.5 = 272$

$1,081 + 3,706 + 614 + 3,268 + 619 + 272 = 9,560$

**Yellow**

WB Decel 352

WB Accel 274

Maintenance Lot  $600 + 217 = 817$

Ramp 509

I-490  $1,772 + 1,787 = 3,559$

$352 + 274 + 817 + 509 + 3,559 = 5,511$



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 48 (MP 390.13) Additional  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

White

Cashless  $134 + 948 + 245 + 650 + 104 = 2,081$

Skip  $375 + 468 + 80 + 77 = 1,000 \times 0.25 = 250$

Stop Bar  $25 \times 4 = 100$

$2,081 + 250 + 100 = 2,431$

Yellow

Maintenance Lot  $65 \times 2 = 130$

Cashless  $(228 \times 2) + 1,250 = 1,706$

$130 + 1,706 = 1,836$



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 48A (MP 401.72) Additional  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

White

Cashless  $117 + 149 + 82 + 92 + 141 + 951 + 974 = 2,506$

Skip  $95 + 71 + 277 + 251 + 75 + 196 + 195 + 252 + 240 = 1,652 \times 0.25 = 413$

Stop Bar  $37 \times 4 = 148$

$2,506 + 413 + 148 = 3,067$

Yellow

Cashless  $1,240 + 565 = 1,805 \times 2 = 3,610$

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Interchange 49 (MP 417.27)  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White**

WB Decel  $2,244 + 1,139 = 3,383$

EB Decel  $3,070 + 1,152 = 4,222$

EB Accel  $2,758 + 1,286 = 4,044$

WB Accel  $2,565 + 1,207 = 3,772$

Intersection  $158 + 158 = 316$

Gore  $541 + 541 + 286 + 492 + 465 + 349 + 259 + 259 + 262 + 262 = 3,716 \times 2 = 7,432$

Skip  $240 + 225 + 1,691 + 1,352 + 1,814 = 5,322 \times 0.25 = 1,331$

Crosswalks  $696 + 176 = 872$

Stop Bar  $42 \times 4 = 168$

$3,383 + 4,222 + 4,044 + 3,772 + 316 + 7,432 + 1,331 + 872 + 168 = 25,540$

**Yellow**

WB Decel 3,905

EB Decel 671

EB Accel 936

WB Accel 4,245

Intersection  $340 + 344 + 173 + 173 + 54 + 54 + 81 + 86 = 1,305$

$3,905 + 671 + 936 + 4,245 + 1,305 = 11,062$

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Service Areas  
White/Yellow/Blue Epoxy Stripes

SHEET # 1 OF 1

### Scottsville Service Area EB

#### White

Decel 1,065

Accel 1,823

Gores  $312 + 261 = 573 \times 2 = 1,146$

$1,065 + 1,823 + 1,146 = 4,034$

#### Yellow

Accel 402

Tractor Trailer  
Parking 2,704

$402 + 2,704 = 3,106$

### Ontario Service Area WB

#### White

Decel 1,007

Accel 1,152

Gores  $167 + 290 = 457 \times 2 = 914$

Gas Station  $114 + 99 + 60 + 20 + 20 + 86 + 30 = 429$

$1,007 + 1,152 + 914 + 429 = 3,502$

#### Yellow

Decel 130

Accel 567

Tractor Trailer  
Parking  $156 + 449 + 449 + 958 + 583 + 558 + 567 + 130 = 3,850$

$130 + 567 + 3,850 = 4,547$

#### Blue

Handicapped  
Parking Square 48

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Rest Areas  
White/Yellow/Blue Epoxy Stripes

SHEET # 1 OF 1

**Rest Area @ MP 318.20 WB**

White

Decel      1,429

Accel      1,400

Gores       $245 + 246 = 491 \times 2 = 982$

$1,429 + 1,400 + 982 = 3,811$

Yellow

Accel      225

Decel      450

$225 + 450 = 675$

**Text Stop @ MP 353.10 EB**

White

Decel      1,520

Accel      1,700

Gores       $228 + 242 = 470 \times 2 = 940$

Skip       $317 \times 0.25 = 80$

Parking      570

$1,520 + 1,700 + 940 + 80 + 570 = 4,810$

Yellow  
1,059

Blue

Handicapped  
Parking Square      96



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/9/2023

SUBJECT: White Pavement Letters

SHEET # 1 OF 1

---

---

ITEM 685.1306--25 - WHITE EPOXY REFLECTORIZED PAVEMENT LETTERS (EA)

Interchange 45

6 " O "

6 " N "

6 " L "

5 " Y "

2 " T "

1 " A "

1 " D "

1 " E "

1 " M "

29 total letters

Interchange 46

2 " O "

2 " N "

2 " L "

1 " Y "

2 " T "

1 " A "

1 " D "

1 " E "

1 " M "

13 total letters

SAY: 42 EA



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: White Pavement Symbols

SHEET # 1 OF 1

---

---

**ITEM 685.1406--25 - WHITE EPOXY REFLECTORIZED PAVEMENT SYMBOLS (EA)**

Interchange 45

- 2 Left Only Arrows
- 2 Right Only Arrows
- 3 Lane Reduction Arrows

Additional Striping @ Interchange 48

- 2 Left Only Arrows
- 1 Right Only Arrow
- 1 Straight Arrow

Additional Striping @ Interchange 48A

- 4 Left Only Arrows
- 2 Right Only Arrows

Mainline MP 349.6 - 378.2

- 4 Lane Reduction Arrows

Interchange 46

- 4 Straight Arrows
- 15 Yield Bar Triangles

Text Stop @ MP 353.10 EB

- 2 Handicapped Parking Symbols

Ontario Service Area

- 1 Handicapped Parking Symbol

Additional Striping @ Interchange 47

- 1 Lane Reduction Arrow

Interchange 49

- 2 Left Only Arrows
- 2 Right Only Arrow
- 2 Left/Straight Arrows

**SAY: 50 EA**





PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Black Pavement Markings

SHEET # 1 OF 1

---

---

ITEM 685.15----25 - BLACK EPOXY PAVEMENT MARKINGS (LF)

MP 289.30 - MP 304.5 40,128 LF

MP 349.60 - MP 351.38 16,752 LF

Interchange 45 258 LF

40,128 + 16,752 + 258 = 57,138

57,138 x 5% = 60,000

SAY: 60,000 LF



PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: White Triple Drop Stripe

SHEET # 1 OF 1

---

---

ITEM 685.1707--25 - WHITE HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP 289.10 - MP 320.70                      417,120 LF

MP 349.60 - MP 378.20                      381,071 LF

MP 404.70 - MP 419.40                      194,040 LF

417,120    +    381,071    +    194,040    =    992,231

992,231    x    5%    =    1,041,850

**SAY: 1,041,850 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the Buffalo and Syracuse Divisions

MADE BY: J. McCool

DATE: 09/2023

CHECKED BY: TJW

DATE: 11/8/2023

SUBJECT: Yellow Triple Drop Stripe

SHEET # 1 OF 1

---

---

ITEM 685.1708--25 - YELLOW HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP 289.10 - MP 320.70                      333,696 LF

MP 349.60 - MP 378.20                      302,016 LF

MP 404.70 - MP 419.40                      155,232 LF

333,696    +    302,016    +    155,232    =    790,944

790,944    x    5%    =    830,500

**SAY: 830,500 LF**