

## **TAS 24-20B / D214978**

### **Replacement of the I-90 Bridge over Oriskany Boulevard (NY 69) at Milepost 238.22 in Oneida County**

#### **QUESTIONS AND ANSWERS**

- Q1. The specified minimum section modulus of 89.28 in<sup>3</sup>/ft for the interim steel sheeting exceeds available products. Please confirm this is correct. If so, this project may require grouted tiebacks and walers with a lower section modulus sheet pile requirement, or a soldier pile and lagging wall.
- A1. The specified minimum section modulus will be revised to 78 in<sup>3</sup>/ft for the interim steel sheeting as part of a forthcoming amendment. This minimum section modulus will allow for Nucor Skyline NZ 42 (or an equivalent) section of sheeting to be utilized.

#### **May 22, 2024**

- Q2. It appears the bid quantity for 556.0203 is not nearly enough according to the bar list in the plans.
- A2. The information in the bar list in the plans is correct, however, the quantity shown in the proposal book and quantity work up sheets is incorrect. The quantity for Item 556.0203 will be revised from 54,500 pounds to 100,000 pounds as part of a forthcoming amendment.