



2" MILL AND INLAY, SAFETY WORK AND
MISCELLANEOUS IMPROVEMENTS
MP 261.7 TO 268.0
D215024
MADISON COUNTY
TAS 25-12

DATE: 08/15/2025
PREPARED BY: ALR
CHECKED BY:
COMP DATE:

ITEM 490.30 (SY)				
MISCELLANEOUS COLD MILLING OF BITUMINOUS CONCRETE				
FROM STATION	LENGTH (FT)	WIDTH (FT)	AREA (SF)	AREA (SY)
FULL U-TURN MP 262.6	CAD-MEASURED AREA		26265	2,918
FULL U-TURN MP 263.88	CAD-MEASURED AREA		11425	1,269
FULL U-TURN MP 266.05	CAD-MEASURED AREA		10280	1,142
FULL U-TURN MP 266.71	CAD-MEASURED AREA		13095	1,455
VERTICAL CLEARANCE, STD. SHT. TA 404-01 AND TA 404-03				
BIN 5512780, MP 263.03 INDIAN OPENING ROAD - EASTBOUND	315	39	12285	1,365
BIN 5512780, MP 263.03 INDIAN OPENING ROAD - WESTBOUND	505	39	19695	2,188
BIN 5512770, MP 265.99 GEE ROAD - EASTBOUND	325	39	12675	1,408
BIN 5512770, MP 265.99 GEE ROAD - WESTBOUND	295	39	11505	1,278
BIN 5512770, MP 265.99 GEE ROAD - WESTBOUND - U-TURN DECEL TAPER	CAD-MEASURED AREA		960	107
BIN 5512750, MP 267.89 LAKEPORT ROAD - EASTBOUND	375	39	14625	1,625
BIN 5512750, MP 267.89 LAKEPORT ROAD - WESTBOUND	375	39	14625	1,625
CHITTENANGO SERVICE AREA	CADD MEASURED		60800	6,756
WB PARTIAL DEPTH REPLACEMENT	WB PDR ITEM CALCS			968
EB PARTIAL DEPTH REPLACEMENT	EB PDR ITEM CALCS			811
			TOTAL:	24,916
			2% CONTINGENCY	498
			SAY:	25,415