

**TAB 25-17B / D215040**  
**Bridge Replacement at Interchange 46 over Thruway (I-90) and**  
**Overhead Sign Structure Replacement at Milepost 362.44**  
**in Monroe County**

**QUESTIONS AND ANSWERS**

**September 17, 2025**

Q1. Cross sections are not provided. Please provide cross sections for the following stations:  
A 12+00 through A 30+00, F 10+00 through F 15+54, and H 10+00 through H14+19

A1. Cross sections will be provided via additional supplemental information.

**September 19, 2025**

Q2. Drawing Number ST-56, Bar List for Superstructure Slab shows 392 of the 6SG9 bars.  
Should this quantity be 784? This will add 6,279 lbs. to the superstructure.

A2. Yes, the quantity of 6SG9 bars should be increased to 784. However, this does not change any item quantities in the estimate as this bar is to be paid for under the superstructure slab item. This plan drawing may be updated in a future amendment.

**September 25, 2025**

Q3. There is concern about the completion date of the project with normal spec. limitations.  
Therefore, we request clarification on the completion date. The piles cannot be driven until the embankment is brought to a certain elevation.

A3. Schedule is to remain the same. To minimize earthwork prior to driving piles, the limit of fill may be reduced to a vertical line taken at the intersection of a 1:1 slope from the edge of the footing to the existing ground.