

TAA 25-27B / D215051
Replacement of the Malden Turnpike (CR34) Bridge
Over NYS Thruway (I-87) in Ulster County

QUESTIONS AND ANSWERS

October 28, 2025

- Q1. Drawing ST-1 identifies borings taken as B-1, B-2 & B-3. Are these borings available for review and to assist with evaluating the means and methods needed for the pile installations?
- A1. Boring logs and foundation design report will be uploaded to the Thruway website as supplemental information for TAA 25-27B.
- Q2. Can you please identify the location for the installation and where the details are for the proposed Armorless Bridge Joint System (Bid Item 567.60)?
- A2. Item 567.60 was included by error. The intent is to install joint seal as per the plan details on ST-35, to be paid for under item 567.63. The proposed joint seal is to be installed between the approach slab end and sleeper slab interface. This will be clarified in a forthcoming Amendment.