

## **PAY ITEM QUANTITY CALCULATIONS**

*INSTALLATION OF PAVEMENT MARKINGS AT VARIOUS LOCATIONS IN THE  
NEW YORK DIVISION*

TANY 25-34

D215065

PIN N72323

H378.1



**Thruway  
Authority**

**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 9/25

Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25

**SUBJECT:** WZTC **SHEET #** 1 **OF** 1

---

---

**ITEM 619.0101 - BASIC WORK ZONE TRAFFIC CONTROL (DAILY OPERATIONS) (LS)**

**1 LS**



**Thruway  
Authority**

**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 9/25

Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25

**SUBJECT:** WZTC **SHEET #** 1 **OF** 1

---

---

**REMOVE PAVEMENT MARKING LETTERS OR SYMBOLS, EPOXY PAINT**

Cross Westchester Espressway - Interchange 12

5 Yield Bar Triangles

**5 EA**

**SAY: 5 EA**



**Thruway  
Authority**

**PROJECT:** Installation of Pavement Markings at Various  
Locations in the New York Division

**MADE BY:** A. Lorini

**DATE:** 9/25

**CHECKED BY:** J. McCool

**DATE:** 10/2/25

**SUBJECT:** Nighttime Operations

**SHEET #** 1 **OF** 1

---

---

**ITEM 619.24 - NIGHTTIME OPERATIONS (LS)**

**1 LS**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Cleaning and Prep of Pavement SHEET # 1 OF 1

---

---

**ITEM 635.01030625 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - 6" WIDTH LINES (LF)**

Item is to be used A.O.B.E.

**SAY: 1,000 LF**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Cleaning and Prep of Pavement - Letters SHEET # 1 OF 2

---

---

**ITEM 635.0203 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - LETTERS (EA)**

Interchange 3

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange 6A

6 " O "  
6 " N "  
6 " L "  
6 " Y "

24 total letters

Interchange 8/8A

4 " O "  
4 " N "  
4 " L "  
4 " Y "

16 total letters

Interchange 9

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange 12

11 " O " 1 "Y"  
11 " N " 1 "E"  
11 " L " 1 "I"  
11 " Y " 1 "L"  
1 "D"

49 total letters

Interchange 15A

9 " O "  
9 " N "  
9 " L "  
9 " Y "

36 total letter

Interchange 16

15 " O "  
15 " N "  
15 " L "  
15 " Y "

60 total letters

Interchange CWE 1

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters

Interchange CWE 2

9 " O "  
9 " N "  
9 " L "  
9 " Y "

36 total letters

Interchange CWE 4

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange CWE 6

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters



PROJECT: <u>Installation of Pavement Markings at Various</u>	MADE BY: <u>A. Lorini</u>	DATE: <u>09/2025</u>
<u>Locations in the New York Division</u>	CHECKED BY: <u>J. McCool</u>	DATE: <u>10/2/25</u>
SUBJECT: <u>Cleaning and Prep of Pavement - Letters</u>	SHEET # <u>2</u> OF <u>2</u>	

**ITEM 635.0203 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - LETTERS (EA)**

Interchange CWE 7

6 " O "  
6 " N "  
6 " L "  
6 " Y "

24 total letters

Interchange CWE 8/8W/8E

8 " O "  
8 " N "  
8 " L "  
8 " Y "

32 total letters

Interchange CWE 9

4 "N"	4 "L"
4 "O"	4 "O"
	4 "W"
4 "T"	
4 "R"	4 "B"
4 "U"	4 "R"
4 "C"	4 "I"
4 "K"	4 "D"
4 "S"	4 "G"
	4 "E"

68 total letters

Interchange CWE 10

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters

Interchange CWE 11

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

SAY: 144 EA THIS PAGE

SAY: 417 EA TOTAL ITEM



**PROJECT:** Installation of Pavement Markings at Various  
Locations in the New York Division

**MADE BY:** A. Lorini

**DATE:** 09/2025

**CHECKED BY:** J. McCool

**DATE:** 10/2/25

**SUBJECT:** Cleaning and Prep of Pavement - Symbols

**SHEET #** 1 **OF** 2

---

---

**ITEM 635.0303--25 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - SYMBOLS (EA)**

**Interchange 3**

- 3 Left Turn Arrows
- 2 Left / Straight Arrows

**Interchange 6A**

- 6 Right Turn Arrows
- 3 Left / Straight Arrows

**Ardsley SA**

- 9 Straight Arrows

**Interchange 8/8A**

- 2 Right/Straight Arrows
- 5 Left Turn Arrows
- 10 Yield Bar Triangles

**Interchange 9**

- 5 Right Turn Arrows
- 2 Left Turn Arrows
- 7 Left / Straight Arrows

**Interchange 10**

- 2 Lane Reduction Arrows

**Interchange 12**

- 15 Preferential Lane Arrows
- 4 Right Turn Arrows
- 4 Lane Reduction Arrows
- 5 Left Turn Arrows
- 2 Left / Straight Arrows
- 6 Straight Arrows
- 13 Yield Bar Triangles

**Interchange 13**

- 4 Left Only Arrows
- 9 Yield Bar Triangles

**Interchange 14A**

- 2 Lane Reduction Arrows
- 4 Yield Bar Triangles

**Interchange 15**

- 2 Lane Reduction Arrows

**Interchange 15A**

- 3 Right Turn Arrows
- 6 Left Turn Arrows
- 11 Yield Bar Triangles

**Interchange 16**

- 14 Right Turn Arrows
- 4 Left Turn Arrows
- 2 Lane Reduction Arrows

**Plattekill SA**

- 1 Handicapped Parking Symbol

**Interchange 18**

- 2 Left Turn Arrows
- 10 Yield Bar Triangles

**Interchange CWE 1**

- 3 Left Turn Arrows
- 5 Yield Bar Triangles

**SAY: 186 EA This sheet**





**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 09/2025  
Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25  
**SUBJECT:** Cleaning and Prep of Pavement - Symbols **SHEET #** 2 **OF** 2

**ITEM 635.0303--25 - CLEANING AND PREPARATION OF PAVEMENT SURFACES - SYMBOLS (EA)**

**Interchange CWE 2**

5 Left Turn Arrows  
6 Right Turn Arrows  
2 Left / Straight Arrows

**Interchange CWE 4**

4 Right Turn Arrows  
4 Left / Straight Arrows

**Interchange CWE 6**

3 Right Turn Arrows  
1 Left Turn Arrows  
2 Left / Right Arrows

**Interchange CWE 7**

6 Left Turn Arrows  
3 Lane Reduction Arrows

**Interchange CWE 8/8W/8E**

4 Left Turn Arrows  
5 Straight Arrows  
2 Right Turn Arrows  
3 Left Straight Arrows  
3 Right Straight Arrows  
2 Lane Reduction Arrows

**Interchange CWE 9**

3 Right Turn Arrows  
3 Straight Arrows

**Interchange CWE 10**

2 Right Turn Arrows  
2 Left / Straight Arrows

**Interchange CWE 11**

3 Right Turn Arrows

**Interchange 1**

3 Left/Straight/Right Arrows

**SAY: 71 EA This sheet**

**SAY: 258 EA Total Item**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Misc. Abrading of Epoxy Stripes SHEET # 1 OF 1

---

---

**ITEM 635.0402--25 - MISCELLANEOUS ABRADING OF EPOXY PAVEMENT STRIPES (LF)**

Item is to be used A.O.B.E.

**SAY: 1,000 LF**

PROJECT: Installation of Pavement Markings at Various      MADE BY: A. Lorini      DATE: 09/2025  
Locations in the New York Divisions      CHECKED BY: J. McCool      DATE: 10/2/25  
SUBJECT: Blue Paint      SHEET # 1 OF 1

**ITEM 640.25000010 - BLUE REFLECTORIZED PAVEMENT MARKING PAINT FOR  
HANDICAPPED PARKING SPACES (LF)**

Service Areas

Platekill SA

48 LF

$$48 \quad \times \quad 5\% \quad = \quad 55$$

**SAY: 55 LF**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Divisions HECKED BY: J.McCool DATE: 10/2/25

SUBJECT: White Epoxy Stripe SHEET # 1 OF 3

---

---

**ITEM 685.0106--25 - WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)**

\*\*All measurements  
were taken using Google

<u>Location</u>	<u>Quantity</u>				
<u>Interchange 1</u>	5691.00	<u>Interchange 15</u>	28182.00	<u>Interchange CWE 9</u>	29074.00
<u>Interchange 2</u>	3015.00	<u>Interchange 15A</u>	9543.00	<u>Interchange CWE 10</u>	5247.00
<u>Interchange 3</u>	4324.00	<u>Ramapo SA</u>	2555.00	<u>Interchange CWE 11</u>	4165.00
<u>Interchange 4</u>	3527.00	<u>Sloatsburg SA</u>	5893.00		
<u>Interchange 5</u>	5289.00	<u>Interchange 16</u>	34973.00	<u>TOTAL</u>	484,761
<u>Interchange 6</u>	14102.00	<u>Plattekill SA</u>	4682.00		
<u>Interchange 6A</u>	16067.00	<u>Interchange 18</u>	24095.00		
<u>Ardsley SA</u>	6194.00	<u>Interchange CWE 1</u>	11557.00		
<u>Interchange 7</u>	4963.00	<u>Interchange CWE 2</u>	6946.00		
<u>Interchange 7A</u>	12703.00	<u>Interchange CWE 3</u>	11702.00		
<u>Interchange 8/8A</u>	42712.00	<u>Interchange CWE 4</u>	9665.00		
<u>Interchange 9</u>	10077.00	<u>Interchange CWE 5</u>	14626.00		
<u>Interchange 10</u>	20397.00	<u>Interchange CWE 6</u>	8995.00		
<u>Interchange 12</u>	19733.00	<u>Interchange CWE 7</u>	21494.00		
<u>Interchange 13</u>	27039.00	<u>Interchange CWE 8/8W/8E</u>	8662.00		
<u>Interchange 14A</u>	27252.00	<u>Interchange CWE 9A</u>	19620.00		

---



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025  
Locations in the New York Division HECKED BY: J. McCool DATE: 10/2/25

SUBJECT: White Epoxy Stripe SHEET # 2 OF 3

**ITEM 685.0106--25 - WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)**

Interchange 3	1	54	Interchange 18	2	31
Interchange 6	1	14	Interchange CWE 1	2	28
Interchange 6A	5	113	Interchange CWE 2	2	45
Ardsey SA	1	11	Interchange CWE 4	3	67
Interchange 7	1	23	Interchange CWE 5	2	42
Interchange 7A	1	14	Interchange CWE 6	2	69
Interchange 8/8A	1	32	Interchange CWE 7	2	48
Interchange 9	3	89	Interchange CWE 8/8W/8E	3	105
Interchange 10	5	126	Interchange CWE 9	1	33
Interchange 12	8	204	Interchange CWE 10	1	49
Interchange 13	4	58			
Interchange 14A	2	58			
Interchange 15A	2	66			
Interchange 16	2	57			

**Total Number of Stop Bars:** **57**

**Total Number of Linear Feet:** **1,436** x **4** = **5,744**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025  
Locations in the New York Division HECKED BY: J. McCool DATE: 10/2/25  
SUBJECT: White Epoxy Stripe SHEET # 3 OF 3

---

---

**ITEM 685.0106--25 - WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)**

**Interchanges**

**Ramp Arrows**

Interchange 7A

2

Interchange 9

1

Interchange 10

5

**Total Linear Feet:**

8 x 74 = **592**

Grand Total: 484,761 + 5,744 + 592 = 491,097

491,097 x 5% = **515,459**

---

**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 09/2025

Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25

**SUBJECT:** Yellow Epoxy Stripe **SHEET #** 1 **OF** 1

**ITEM 685.0206--25 - YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES 6 INCH X 15 MILS (LF)**

\*\*All measurements  
were taken using Google

<u>Location</u>	<u>Quantity</u>			
<u>Interchange 1</u>	1075.00	<u>Interchange 15</u>	12490.00	<u>Interchange 12</u> 205.00
<u>Interchange 2</u>	650.00	<u>Interchange 15A</u>	3556.00	<u>Interchange 18</u> 03.00
<u>Interchange 3</u>	890.00	<u>Ramapo SA</u>	574.00	<u>Interchange 6</u> 43.00
<u>Interchange 4</u>	874.00	<u>Sloatsburg SA</u>	1433.00	
<u>Interchange 5</u>	1362.00	<u>Interchange 16</u>	19470.00	
<u>Interchange 6</u>	4616.00	<u>Plattekill SA</u>	576.00	192,314 x 5% = 202,015
<u>Interchange 6A</u>	3959.00	<u>Interchange 18</u>	13216.00	
<u>Ardsley SA</u>	608.00	<u>Interchange CWE 1</u>	3828.00	
<u>Interchange 7</u>	1836.00	<u>Interchange CWE 2</u>	1674.00	
<u>Interchange 7A</u>	5084.00	<u>Interchange CWE 3</u>	4634.00	
<u>Interchange 8/8A</u>	18735.00	<u>Interchange CWE 4</u>	2192.00	
<u>Interchange 9</u>	3583.00	<u>Interchange CWE 5</u>	5994.00	
<u>Interchange 10</u>	9035.00	<u>Interchange CWE 6</u>	3166.00	
<u>Interchange 12</u>	3717.00	<u>Interchange CWE 7</u>	10943.00	
<u>Interchange 13</u>	12732.00	<u>Interchange CWE 8/8W/8E</u>	3486.00	
<u>Interchange 14A</u>	11708.00	<u>Interchange CWE 9A</u>	9967.00	

**Total: 202,015 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 1      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $419 + 1,106 + 815 + 683 = 3,023$

Gore       $187 + 129 + 231 + 129 + 90 + 63 + 266 + 239 = 1,334 \times 2 = 2,668$

$3,023 + 2,668 = 5,691$

**Total White:      5,691 LF**

**Yellow:**

$104 + 367 + 227 + 377 = 1,075$

**Total Yellow:      1,075 LF**





**Thruway  
Authority**

**PROJECT:** Installation of Pavement Markings at Various  
Locations in the New York Division

**MADE BY:** D. Matthews

**DATE:** 09/2025

**CHECKED BY:** J. McCool

**DATE:** 10/2/25

**SUBJECT:** Interchange 2  
White/Yellow Epoxy Stripes

**SHEET #** 1 **OF** 1

**White:**

Standard 6"  $1.149 + 484 = 1,633$

Gore  $137 + 154 + 237 + 163 = 692 \times 2 = 1,382$

$1,633 + 1,382 = 3,015$

**Total White: 3,015 LF**

**Yellow:**

$514 + 144 = 658$

**Total Yellow: 658 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division MADE BY: D. Matthews DATE: 09/2025  
CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Interchange 3 SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"  $1,208 + 162 + 917 + 176 + 265 = 2,728$   
Gore  $188 + 162 + 917 + 176 + 265 = 798 \times 2 = 1,596$   
Stop Bar  $54 \times 4 = 216$

$$2,728 + 1,596 = 4,324$$

**Total White: 4,324 LF**

**Yellow:**

$$167 + 364 + 359 = 890$$

**Total Yellow: 890 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 4  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"       $590 + 855 = 1,445$

Gore               $342 + 356 + 148 + 195 = 1,041 \times 2 = 2082$

$$1,445 + 2,082 = 3,527$$

**Total White:      3,527 LF**

**Yellow:**

$$266 + 608 = 874$$

**Total Yellow:      874 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division MADE BY: D. Matthews DATE: 09/2025  
CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Interhcnage 5 SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"  $286 + 2,028 + 1,113 = 3,427$   
Gore  $233 + 319 + 379 = 931 \times 2 = 1,862$

$$3,427 + 1,862 = 5,289$$

**Total White: 5,289 LF**

**Yellow:**

$$663 + 699 = 1,362$$

**Total Yellow: 1,362 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 6  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"  $2,101 + 1,727 + 1,293 + 2,248 + 266 + 1,312 + 1,183 = 10,130$

Gore  $220 + 54 + 123 + 40 + 263 + 51 + 116 + 193 + 105 + 114 + 119$   
 $+ 163 + 174 + 169 = 1904 \times 2 = 3,808$

Crosswalk  $56 + 54 + 30 + 24 = 164$

Stop Bar  $14 \times 4 = 56$

$10,130 + 3,808 + 164 = 14,102$

**Total White: 14,102 LF**

**Yellow:**

$647 + 684 + 613 + 1,021 + 171 + 933 + 547 = 4,616$

**Total Yellow: 4,616 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 6A      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,868 + 52 + 35 + 32 + 151 + 1,766 + 1,169 + 546 + 1,822 + 518 + 217 + 1,883 = 10,059$

Gore       $295 + 186 + 60 + 263 + 596 + 251 + 276 + 106 + 169 + 340 = 2,660 \times 2 = 5,320$

Skips       $213 + 1,586 + 423 + 445 = 2,667 + 83 = 2,750 / 4 = 687.5 \sim 688$

Stop Bar       $24 + 25 + 26 + 14 + 24 = 113 \times 4 = 452$

$$10,059 + 5,320 + 688 = 16,067$$

**Total White:      16,067 LF**

**Yellow:**

$$446 + 1,698 + 228 + 565 + 582 + 440 = 3,959$$

**Total Yellow:      3,959 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Ardsley SA      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,094 + 1,445 + 486 + 319 + 192 + 359 + 24 + 80 + 70 + 162 = 4,416$

Gore       $327 + 301 + 261 = 889 \times 2 = 1,778$

Stop Bar       $11 \times 4 = 44$

$4,416 + 1,778 = 6,194$

**Total White:      6,194 LF**

**Yellow:**

$130 + 478 = 608$

**Total Yellow:      608 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 7A  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"       $3,817 + 3,537 + 2,157 = 9,511$

Gore               $408 + 194 + 334 + 336 + 232 + 92 = 1,596 \times 2 = 3,192$

Stop Bar         $14 \times 4 = 56$

$9,511 + 3,192 = 12,703$

**Total White:      12,703 LF**

**Yellow:**

$1,910 + 1,666 + 1,508 = 5,084$

**Total Yellow:      5,084 LF**





PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 7  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"       $1,809 + 1,926 = 3,735$

Gore               $74 + 318 + 222 = 614 \times 2 = 1,228$

Stop Bar         $23 \times 4 = 92$

$3,735 + 1,228 = 4,963$

**Total White:      4,963 LF**

**Yellow:**

$831 + 1,005 = 1,836$

**Total Yellow:      1,836 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 8 & 8A      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"

$$1,965 + 297 + 134 + 1,398 + 4,340 + 743 + 1,093 + 3,808 + 104 + 2,187 + \\ 5,602 + 185 + 1,946 + 1,367 + 1,975 = 27,144$$

Gore

$$339 + 176 + 481 + 260 + 195 + 430 + 401 + 349 + 471 + 141 + 272 + 338 + 289 + \\ 329 + 419 + 444 + 130 + 209 + 204 + 210 + 312 + 93 = 6,492 \times 2 = 12,984$$

Skips

$$2,667 + 2,679 + 689 + 1,956 + 911 + 83 + 1,094 = 10,079 / 4 = 2,519.75 \sim 2,520$$

Stop Bar

$$32 + 16 = 52 \times 4 = 192$$

$$27,144 + 12,984 + 2,520 = 42,712$$

**Total White:      42,712 LF**

**Yellow:**

$$2,668 + 1,662 + 301 + 1,021 + 1,924 + 2,922 + 831 + 1,030 + 1,548 + 4,307 + 521 = 18,735$$

**Total Yellow:      18,735 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 9  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"  $2,200 + 2,041 + 194 + 195 + 1,098 + 81 + 2,353 = 8,162$

Gore  $121 + 197 + 341 + 183 = 842 \times 2 = 1,684$

Stop Bar  $30 + 15 + 44 = 89 \times 4 = 356$

Skips  $80 + 119 + 528 + 47 + 150 = 924 / 4 = 231$

$8,162 + 1,684 + 356 = 10,077$

**Total White: 10,077 LF**

**Yellow:**

$1,017 + 1,070 + 685 + 811 = 3,583$

**Total Yellow: 3,583 LF**



**DATE:** 10/2/25

**SHEET #** 1 **OF** 1

**Total Yellow: 9,035 LF**





Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 13      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,682 + 94 + 1,988 + 1,329 + 3,273 + 3,217 + 2,885 +$   
 $5,078 + 2,029 + 101 = 21,676$

Gore       $93 + 107 + 153 + 169 + 137 + 135 + 155 + 113 + 211 + 104 +$   
 $137 + 142 + 153 + 279 + 165 + 182 = 2,436 \times 2 = 4,870$

Stop Bar       $15 + 28 + 37 + 15 = 95 \times 4 = 380$

Skips       $1,063 + 906 = 1,969 / 4 = 493$

$21,676 + 4,870 + 493 = 27,039$

**Total White:      27,039 LF**

**Yellow:**

$1,080 + 1,416 + 1,785 + 1,028 + 1,794 + 1,991 + 1,638 + 2,400 = 12,732$

**Total Yellow:      12,732 LF**



**DATE:** 10/2/25

**SHEET #** 1 **OF** 1



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Interchange 15  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"

$$1,747 + 417 + 3,885 + 1,593 + 3,462 + 5,787 = 16,891$$

Gore

$$416 + 356 + 589 + 294 + 443 + 634 + 213 + 221 + 217 = 3,383 \times 2 = 6,766$$

Skips

$$4,905 + 4,298 + 2,383 + 520 + 677 + 1,068 + 3,078 + 862 + 312 = 18,103 / 4 = 4,525$$

$$16,891 + 6,766 + 4,525 = 28,182$$

**Total White: 28,182 LF**

**Yellow:**

$$2,699 + 4,451 + 1,846 + 3,494 = 12,490$$

**Total Yellow: 12,490 LF**





PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 15A      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,106 + 78 + 890 + 1,657 + 1,457 + 846 + 163 + 201 = 6,398$

Gore       $381 + 206 + 299 + 197 + 176 = 1,259 \times 2 = 2,518$

Stop Bars       $43 + 23 = 66 \times 4 = 264$

Skips       $1,013 + 439 = 1,452 / 4 = 363$

$6,398 + 2,518 + 363 = 9,543$

**Total White:      9,543 LF**

**Yellow:**

$566 + 854 + 736 + 1,274 + 126 = 3,556$

**Total Yellow:      3,556 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Rampos SA  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"       $1,108 + 713 = 1,821$

Gore               $186 + 181 = 367 \times 2 = 734$

$1,821 + 734 = 2,555$

**Total White:      2,555 LF**

**Yellow:**

574

**Total Yellow:      574 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Sloatsburg SA      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,870 + 1,187 + 18 + 86 + 120 = 3,281$

12"       $10 + 9 + 4 + 3 + 2 + 17 + 5 + 4 + 3 \text{ } 173 = 230 \times 2 = 460$

24"       $(9 \times 29) = 261 \times 4 = 1,044$

Gore       $267 + 198 + 89 = 554 \times 2 = 1,108$

$$3,281 + 460 + 1,044 + 1,108 = 5,893$$

**Total White:      5,693 LF**

**Yellow:**

Standard 6"      673

12"       $136 + (8 \times 9) + 45 + 49 + (13 \times 6) = 380 \times 2 = 760$

$673 + 760 = 1,433$

**Total Yellow:      1,433 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: Interchange 16      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $5,566 + 5,487 + 4,503 + 584 + 296 + 181 + 693 + 149 + 87 + 5,913 = 23,459$

Gore       $122 + 70 + 1,173 + 213 + 149 + 518 + 567 + 111 + 149 + 149 +$   
 $327 = 3,548 \times 2 = 7,096$

Stop Bars       $15 + 42 = 57 \times 4 = 228$

Skips       $4,243 + 6,468 + 520 + 619 + 535 + 1,055 + 1,275 + 356 + 1,150$   
 $+ 382 + 154 = 16,757 / 4 = 4,189.25 \sim 4,190$

$23,459 + 7,096 + 4,190 = 34,973$

**Total White:      34,973 LF**

**Yellow:**

$132 + 1,310 + 2,540 + 5,709 + 6,446 + 1,834 + 679 + 718 + 92 = 19,470$

**Total Yellow:      19,470 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Plattekill SA  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"  $1,771 + 13 + 13 + 13 + 13 + 162 + 1,023 + 144 + 13 + 30 = 3,164$

Gore  $178 + 330 + 47 = 555 \times 2 = 1,110$

Crosswalk  $51 + 51 + 54 = 156 \times 2 = 312$

Hatch Lines  $31 + 11 + 6 = 96$

$3,164 + 1,110 + 312 + 96 = 4,682$

**Total White: 4,682 LF**

**Yellow:**

$556 + 20 = 576$

**Total Yellow: 576 LF**





PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 1      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $2,388 + 178 + 157 + 256 + 138 + 1,046 + 107 + 3,155 =$   
7,425

Gore       $278 + 267 + 210 + 166 + 147 + 245 + 75 + 63 + 232 + 155 =$   
 $1,838 \times 2 = 3,676$

Stop Bars       $114 + 14 = 28 \times 4 = 112$

Skips       $130 + 191 + 557 + 946 = 1,824 / 4 = 456$

$7,425 + 3,676 + 456 = 11,557$

**Total White:      11,557 LF**

**Yellow:**

$226 + 645 + 535 + 1,457 + 180 + 785 = 3,828$

**Total Yellow:      3,828 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 2      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"

$$495 + 861 + 43 + 1,785 = 3,254$$

Gore

$$73 + 182 + 400 + 74 + 121 + 180 = 1,030 \times 2 = 3,060$$

Stop Bars

$$14 + 31 = 45 \times 4 = 180$$

Skips

$$355 + 174 + 175 = 704 / 4 = 176$$

Crosswalk

$$66 + 88 + 30 + 48 + 109 + 126 + 121 + 140 = 728 \times 2 = 1,456$$

$$3,254 + 3,060 + 176 + 1,456 = 6,946$$

**Total White:      6,946 LF**

**Yellow:**

$$592 + 466 + 616 = 1,674$$

**Total Yellow:      1,674 LF**







PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 4      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,028 + 45 + 347 + 1,776 + 1,667 + 857 + 55 + 286 + 33 + 123 = 6,217$

Gore       $414 + 377 + 449 + 185 = 1,425 \times 2 = 2,850$

Skips       $414 / 4 = 103.5 \sim 104$

Crosswalk       $44 + 40 + 50 + 80 = 214 \times 2 = 428$

Stop Bar       $14 + 25 + 28 = 67 \times 4 = 268$

$6,217 + 2,850 + 104 + 428 = 9,600$

**Total White:      9,665 LF**

**Yellow:**

$576 + 618 + 497 + 501$

**Total Yellow:      2,192 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 5      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,863 + 3,271 + 1,576 + 43 + 617 + 2,348 = 9,718$

Gore       $269 + 578 + 104 + 337 + 390 + 36 + 155 = 1,869 \times 2 = 3,738$

Skips       $1,645 / 4 = 411.25 \sim 412$

Crosswalk       $106 + (11 \times 8) + 80 + 105 = 379 \times 2 = 758$

Stop Bar       $14 + 28 = 42 \times 4 = 168$

$9,718 + 3,738 + 412 + 758 = 14,626$

**Total White:      14,626 LF**

**Yellow:**

$1,072 + 2,293 + 670 + 1,959 = 5,994$

**Total Yellow:      5,994 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 6      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $2,060 + 58 + 80 + 612 + 2,332 + 132 + 907 = 6,181$

Gore       $108 + 83 + 133 + 175 + 219 + 220 = 938 \times 2 = 1,876$

Skips       $83 + 239 + 37 = 359 / 4 = 89.75 \sim 90$

Crosswalk       $102 + (14 \times 8) + 106 + (13 \times 8) = 424 \times 2 = 848$

Stop Bar       $36 + 33 = 69 \times 4 = 276$

$6,181 + 1,876 + 90 + 848 = 8,995$

**Total White:      8,995 LF**

**Yellow:**

$59 + 361 + 449 + 613 + 684 = 2,166$

**Total Yellow:      2,166 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 7      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $146 + 304 + 527 + 1,345 + 90 + 460 + 577 + 5,035 + 1,266 + 734 + 2,405 = 12,889$

Gore       $149 + 287 + 220 + 96 + 274 + 166 + 312 + 173 + 365 + 201 + 390 = 2,633 \times 2 = 5,266$

Skips       $103 + 68 + 1,266 + 353 + 2,975 + 4,707 + 2,396 = 11,868 / 4 = 2,967$

Crosswalk       $90 + (12 \times 8) = 186 \times 2 = 372$

Stop Bar       $25 + 23 = 48 \times 4 = 192$

$12,889 + 5,266 + 2,967 + 372 = 21,494$

**Total White:      21,494 LF**

**Yellow:**

$669 + 356 + 749 + 3,912 + 1,733 + 1,529 + 1,995 = 10,943$

**Total Yellow:      10,943 LF**





PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 9A      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $1,233 + 1,771 + 4,107 + 1,049 + 1,554 + 1,451 + 1,551 = 12,716$

Gore       $129 + 150 + 208 + 104 + 385 + 457 + 159 + 259 + 228 + 311 + 197 + 192 = 2,779 \times 2 = 5,558$

Skips       $446 + 634 + 1,919 + 2,384 = 5,383 / 4 = 1,345.75 \sim 1,346$

$12,716 + 5,558 + 1,346 = 19,620$

**Total White:      19,620 LF**

**Yellow:**

$776 + 3,240 + 1,795 + 1,854 + 2,292 = 9,967$

**Total Yellow:      9,967 LF**



PROJECT: Installation of Pavement Markings at Various      MADE BY: D. Matthews      DATE: 09/2025  
Locations in the New York Division      CHECKED BY: J. McCool      DATE: 10/2/25

SUBJECT: CWE Interchange 9      SHEET # 1 OF 1  
White/Yellow Epoxy Stripes

---

---

**White:**

Standard 6"       $539 + 475 + 2,158 + 1,015 + 1,170 + 2,018 + 1,197 +$   
 $2,915 + 924 + 290 + 1,709 + 1,837 + 811 = 16,958$

Gore       $322 + 347 + 191 + 305 + 361 + 301 + 354 + 395 + 97 + 237 +$   
 $250 + 383 + 170 + 240 + 231 + 318 + 146 + 130 + 175 + 184 +$   
 $118 + 163 + 126 + 103 = 5,963 \times 2 = 11,926$

Skips       $760 / 4 = 190$

Stop Bar       $33 \times 4 = 132$

$16,958 + 11,926 + 190 = 29,075$

**Total White:      29,075 LF**

**Yellow:**

$510 + 940 + 1,698 + 340 + 593 + 1,307 + 605 + 948 + 1,540 + 969 + 1,324 + 1,431 = 12,205$

**Total Yellow:      12,205 LF**





PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: CWE Interchange 10  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"

$$250 + 807 + 1,274 + 141 = 2,472$$

Gore

$$307 + 295 + 245 + 199 + 333 = 1,379 \times 2 = 2,758$$

Skips 68 / 4 = 17

Stop Bar 49 x 4 = 196

$$2,472 + 2,758 + 17 = 5,247$$

**Total White: 5,247 LF**

**Yellow:**

$$645 + 479 + 679 = 1,803$$

**Total Yellow: 1,803 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: D. Matthews

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: CWE Interchange 11  
White/Yellow Epoxy Stripes

SHEET # 1 OF 1

**White:**

Standard 6"       $72 + 1,190 + 1,421 = 2,683$

Gore               $225 + 114 + 119 = 458 \times 2 = 916$

Skips              $150 / 4 = 37.5 \sim 38$

Crosswalk        $(7 \times 20) + 67 + 57 = 264 \times 4 = 528$

$2,683 + 916 + 38 = 4,165$

**Total White:      4,165 LF**

**Yellow:**

$416 + 227 = 643$

**Total Yellow:      643 LF**



PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: White Epoxy ReflectORIZED Pavement Letters SHEET # 1 OF 2

---

---

**ITEM 685.1306--25 - WHITE EPOXY REFLECTORIZED PAVEMENT LETTERS (EA)**

Interchange 3

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange 6A

6 " O "  
6 " N "  
6 " L "  
6 " Y "

24 total letters

Interchange 8/8A

4 " O "  
4 " N "  
4 " L "  
4 " Y "

16 total letters

Interchange 9

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange 12

11 " O " 1 "Y"  
11 " N " 1 "E"  
11 " L " 1 "I"  
11 " Y " 1 "L"  
1 "D"

49 total letters

Interchange 15A

9 " O "  
9 " N "  
9 " L "  
9 " Y "

36 total letter

Interchange 16

15 " O "  
15 " N "  
15 " L "  
15 " Y "

60 total letters

Interchange CWE 1

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters

Interchange CWE 2

9 " O "  
9 " N "  
9 " L "  
9 " Y "

36 total letters

Interchange CWE 4

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

Interchange CWE 6

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters



<b>PROJECT:</b> <u>Installation of Pavement Markings at Various</u>	<b>MADE BY:</b> <u>A. Lorini</u>	<b>DATE:</b> <u>09/2025</u>
<u>Locations in the New York Division</u>	<b>CHECKED BY:</b> <u>J. McCool</u>	<b>DATE:</b> <u>10/2/25</u>
<b>SUBJECT:</b> <u>White Epoxy ReflectORIZED Pavement Letters</u>	<b>SHEET #</b> <u>2</u> <b>OF</b> <u>2</u>	

**ITEM 685.1306--25 - WHITE EPOXY REFLECTORIZED PAVEMENT LETTERS (EA)**

Interchange CWE 7

6 " O "  
6 " N "  
6 " L "  
6 " Y "

24 total letters

Interchange CWE 8/8W/8E

8 " O "  
8 " N "  
8 " L "  
8 " Y "

32 total letters

Interchange CWE 9

4 "N"	4 "L"
4 "O"	4 "O"
	4 "W"
4 "T"	
4 "R"	4 "B"
4 "U"	4 "R"
4 "C"	4 "I"
4 "K"	4 "D"
4 "S"	4 "G"
	4 "E"

68 total letters

Interchange CWE 10

2 " O "  
2 " N "  
2 " L "  
2 " Y "

8 total letters

Interchange CWE 11

3 " O "  
3 " N "  
3 " L "  
3 " Y "

12 total letters

**SAY: 144 EA THIS PAGE**

**SAY: 417 EA TOTAL ITEM**

**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 09/2025

Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25

**SUBJECT:** White Epoxy ReflectORIZED Pavement Symbols **SHEET #** 1 **OF** 2

**ITEM 685.1406--25 - WHITE EPOXY REFLECTORIZED PAVEMENT SYMBOLS (EA)**

**Interchange 3**

- 3 Left Turn Arrows
- 2 Left / Straight Arrows

**Interchange 6A**

- 6 Right Turn Arrows
- 3 Left / Straight Arrows

**Ardsley SA**

- 9 Straight Arrows

**Interchange 8/8A**

- 2 Right/Straight Arrows
- 5 Left Turn Arrows
- 10 Yield Bar Triangles

**Interchange 9**

- 5 Right Turn Arrows
- 2 Left Turn Arrows
- 7 Left / Straight Arrows

**Interchange 10**

- 2 Lane Reduction Arrows

**Interchange 12**

- 15 Preferential Lane Arrows
- 4 Right Turn Arrows
- 4 Lane Reduction Arrows
- 5 Left Turn Arrows
- 2 Left / Straight Arrows
- 6 Straight Arrows
- 13 Yield Bar Triangles

**Interchange 13**

- 4 Left Only Arrows
- 9 Yield Bar Triangles

**Interchange 14A**

- 2 Lane Reduction Arrows
- 4 Yield Bar Triangles

**Interchange 15**

- 2 Lane Reduction Arrows

**Interchange 15A**

- 3 Right Turn Arrows
- 6 Left Turn Arrows
- 11 Yield Bar Triangles

**Interchange 16**

- 14 Right Turn Arrows
- 4 Left Turn Arrows
- 2 Lane Reduction Arrows

**Plattekill SA**

- 1 Handicapped Parking Symbol

**Interchange 18**

- 2 Left Turn Arrows
- 10 Yield Bar Triangles

**Interchange CWE 1**

- 3 Left Turn Arrows
- 5 Yield Bar Triangles

**SAY: 187 EA This sheet**



**PROJECT:** Installation of Pavement Markings at Various **MADE BY:** A. Lorini **DATE:** 09/2025  
Locations in the New York Division **CHECKED BY:** J. McCool **DATE:** 10/2/25  
**SUBJECT:** Cleaning and Prep of Pavement - Symbols **SHEET #** 2 **OF** 2

**ITEM 685.1406--25 - WHITE EPOXY REFLECTORIZED PAVEMENT SYMBOLS (EA)**

**Interchange CWE 2**

5 Left Turn Arrows  
6 Right Turn Arrows  
2 Left / Straight Arrows

**Interchange CWE 4**

4 Right Turn Arrows  
4 Left / Straight Arrows

**Interchange CWE 6**

3 Right Turn Arrows  
1 Left Turn Arrows  
2 Left / Right Arrows

**Interchange CWE 7**

6 Left Turn Arrows  
3 Lane Reduction Arrows

**Interchange CWE 8/8W/8E**

4 Left Turn Arrows  
5 Straight Arrows  
2 Right Turn Arrows  
3 Left Straight Arrows  
3 Right Straight Arrows  
2 Lane Reduction Arrows

**Interchange CWE 9**

3 Right Turn Arrows  
3 Straight Arrows

**Interchange CWE 10**

2 Right Turn Arrows  
2 Left / Straight Arrows

**Interchange CWE 11**

3 Right Turn Arrows

**Interchange 1**

3 Left/Straight/Right Arrows

**SAY: 71 EA This sheet**

**SAY: 258 EA Total Item**



**Thruway  
Authority**

**PROJECT:** Installation of Pavement Markings at Various  
Locations in the New York Division

**MADE BY:** A. Lorini

**DATE:** 9/25

**CHECKED BY:** J. McCool

**DATE:** 10/2/25

**SUBJECT:** Black Pavement Markings

**SHEET #** 1 **OF** 1

---

---

**ITEM 685.15----25 - BLACK EPOXY PAVEMENT MARKINGS (LF)**

Interchange 9 132 LF

Interchange 12 456 LF

Interchange 15 3,622 LF

Interchange 15A 363 LF

$$4,573 \quad \times \quad 5\% \quad = \quad 4,810$$

**SAY: 4,810 LF**



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J.McCool DATE: 10/2/25

SUBJECT: White Highly Reflectorized Triple Drop Epoxy Stripe SHEET # 1 OF 1

---

---

**ITEM 685.1707--25 - WHITE HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)**

MP CW 0.00 - MP CW 10.90 EB/WB 172,986 LF

172,986 x 5% = 181,640

**SAY: 181,640 LF**





Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various MADE BY: A. Lorini DATE: 09/2025

Locations in the New York Division CHECKED BY: J. McCool DATE: 10/2/25

SUBJECT: Yellow Highly ReflectORIZED Triple Drop Epoxy Stripe SHEET # 1 OF 1

---

---

**ITEM 685.1708--25 - YELLOW HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)**

MP CW 0.00 - MP CW 10.90 EB/WB 115,104 LF

115,104 x 5% = 120,860

**SAY: 120,860 LF**



PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: A. Lorini

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Preformed Thermoplastic Pavement Letters

SHEET # 1 OF 1

---

**ITEM 687.20800125 - MULTI-COLOR PREFORMED THERMOPLASTIC REFLECTORIZED PAVEMENT LETTERS (EA)**

Governor Mario M. Cuomo Bridge Path

LETTERS/QTY:

"S" - 5

"L" - 8

"O" - 8

"W" - 7

"P" - 9

"E" - 23

"D" - 4

"H" - 17

"U" - 7

"M" - 8

"A" - 9

"T" - 1

106 EACH



Thruway  
Authority

PROJECT: Installation of Pavement Markings at Various  
Locations in the New York Division

MADE BY: A. Lorini

DATE: 09/2025

CHECKED BY: J. McCool

DATE: 10/2/25

SUBJECT: Preformed Thermoplastic Pavement Symbol

SHEET # 1 OF 1

---

**ITEM 687.20800225 - MULTI-COLOR PREFORMED THERMOPLASTIC REFLECTORIZED PAVEMENT SYMBOLS (EA)**

Governor Mario M. Cuomo Bridge Path

<u>SYMBOL:</u>	<u>QTY:</u>
"Speed Limit 15 MPH" -	20
"Chevron Pair" -	40
"Bike Rider Symbol" -	31
"Walking Symbol" -	29
"Mile Break Details" -	4
"5 MPH" -	5

129 **EACH**